RECORD OF BIDS - Elm Avenue Paving Projects L-M-262(3)

Date of Letting: February 14, 2006, 9:00 AM

Washington County

Kind of Work: Paving
Project L-M-262(3)

					Fred Carslon Co., LLC		Flynn Company, Inc.		Manatt's, Inc.	
NO	**ITEM**	**Quantity**	**UNIT**		**Unit Price**	**Amount**	**Unit Price**	**Amount**	**Unit Price**	**Amount**
1	Granular Shoulders, Type 'B'	14,927.00	ton		12.90	$192,558.30	11.90	$177,631.30	12.85	$191,811.95
2	Shoulder Construction, Earth	409.10	sta		25.00	$10,227.50	40.00	$16,364.00	76.00	$31,091.60
3	Relocation of Mail Boxes	6.00	each		50.00	$300.00	75.00	$450.00	175.00	$1,050.00
4	Rumble Strip Panel (PCC Surface)	3.00	Each		100.00	$300.00	150.00	$450.00	275.00	$825.00
5	Pavement PCC Slip Form, Furnish Only	12,199.54	cy		72.11	$879,708.83	66.00	$805,169.64	75.35	$919,235.34
6	Pavement PCC Slip Form, Place Only	54,898.00	sy		3.60	$197,632.80	4.84	$265,706.32	3.90	$214,102.20
7	Surfacing, Driveway, CL A Crushed Stone	147.00	ton		15.00	$2,205.00	12.90	$1,896.30	13.40	$1,969.80
8	Removal of Pavement	47.50	sy		10.00	$475.00	18.00	$855.00	24.00	$1,140.00
9	Safety Closure	7.00	each		140.00	$980.00	140.00	$980.00	74.00	$518.00
10	Painted Pavement Markings, Waterborne/Solvent	635.19	sta		11.79	$7,488.89	11.79	$7,488.89	13.90	$8,829.14
11	Traffic Control	1.00	ls		3,250.00	$3,250.00	1,500.00	$1,500.00	3,255.00	$3,255.00
12	Flaggers	2.00	day		200.00	$400.00	300.00	$600.00	350.00	$700.00
13	Mobilization	1.00	ls		28,600.00	$28,600.00	59,000.00	$59,000.00	27,000.00	$27,000.00
14	Clean-out of Silt Fence	1,553.00	lf		1.00	$1,553.00	1.00	$1,553.00	1.75	$2,717.75
15	Clean-out of Silt Fence for Ditch Check	1,746.00	lf		1.00	$1,746.00	1.50	$2,619.00	1.75	$3,055.50
			TOTALS			$1,327,425.32		$1,342,263.45		$1,407,301.28